

VIJAYAWADA MUNICIPAL CORPORATION
NURM
PROPOSALS FOR WATER SUPPLY SCHEMES

Sl. No.	Name of the Work	Estimate Amount Rs. in Lakhs
1	Providing G.L.S.R. on hill top of Syed Appala Swamy College for distribution	270.00
2	Providing E.L.S.R.s in the following areas for distribution	
a	1500 KL at Labbipet area.	270.00
b	1500 KL at Patamatalanka area	270.00
c	1500 KL at Kandrika	270.00
d	1500 KL at Singh Nagar	270.00
e	1200 KL at Kabela	270.00
f	1200 KL at Gollapalem Gattu	270.00
g	1200 KL near to KBN College	270.00
h	1200 KL on canal bund near Bundar Locks	270.00
l	1200 KL at Sundaraiah Nagar near Payakapuram	270.00
2	Providing Distribution net work in various unserved areas with HDEP Pipes with size ranging from 100mm to 500mm	13500.00
3	Providing Distribution net work in existing areas duly replacing old and damaged pipes with HDPE Pipes and Ductile Iron pipes.	6750.00
4	Providing pumping mains for various ELSRs	
a	900mm pumping main along karakatta in one town area.	3825.00
b	Providing 400mm dia pumping main to KBN College proposed ELSR	90.00
c	Providing 600mm dia pumping main from Prakash Nagar Fire Station to NSC Bose Nagar (2 Kms.)	765.00
d	Providing 400mm dia pumping main from NSC Bose Nagar to Kandrika.	337.50
e	providing diversion arrangementsto the existing PSC pumping main600mm main	810.00
f	Providing 900mm dia pumping main from head water works compound to the kalakshatram	4050.00
g	Providing 600mm dia pumping main from common point to the labbipet reservior	1350.00
h	Providing 600mm dia pumping main from common point to the karmikanagar reservior	450.00

VIJAYAWADA MUNICIPAL CORPORATION
NURM
PROPOSALS FOR WATER SUPPLY SCHEMES

Sl. No.	Name of the Work	Estimate Amount Rs. in Lakhs
5	Providing 900mm dia pumping main from head water works compound to the zyamkhana club road.	4500.00

VIJAYAWADA MUNICIPAL CORPORATION
NURM
PROPOSALS FOR WATER SUPPLY SCHEMES

Sl. No.	Name of the Work	Estimate Amount Rs. in Lakhs
a	Providing 600mm dia pumping main from common point to the mach factory reservior	1800.00
b	construction of the under ground sump for clear water storage of 10 M.G.D capacity	225.00
c	conversion of the existing 5M.G.d filtration plant into the dueal media filters to augment the capacity.	90.00
d	supply delivery and the erection of the 400Hp capacity pump sets in head works	360.00
e	Construction of 10 M.G.D. Filtration Plant with rapid sand filters and mechanisation	2250.00
f	Provision for development of surface water treatment facility at Ramalingeswara Nagar including land development, electrical arrangements, pumpsets, canal cross bunding, intake works, sump etc.	4500.00
6	Miscelinious	
a	provision for electrical transformers, feeder lines etc	90.00
b	provisision for the maintenance equipment & testing equipments	90.00
c	provision for the crossing of the pipe lines near durga temple foot of the hill	1800.00
d	Provision for valves, gauges etc.,	225.00
e	Provision for construction of compound walls, watchmen quarters and store sheds at required locations	225.00
f	Provision for SCADA arrangements at Head Water works including mechanization in ancillary units.	1800.00
g	Provision for updation of records, stream lining the administrative procedures etc.	67.50
h	Provision for development of softwares, various packages for engineering activities, computer systems and accessories.	450.00
i	Provision for development of detailed project reports, Master plans and collection of data from time to time.	900.00
	Total	54000.00